

RESOURCE CONSERVATION AND
RECOVERY ACT FACILITY OPERATING
PERMIT

ATTACHMENTS A THROUGH M

EPA ID No. NM5890110518

issued to the

U.S. DEPARTMENT OF ENERGY/SANDIA CORPORATION

for the

SANDIA NATIONAL LABORATORIES
HAZARDOUS AND MIXED WASTE TREATMENT AND
STORAGE UNITS AND POST-CLOSURE CARE OF THE
CORRECTIVE ACTION MANAGEMENT UNIT

located in

BERNALILLO COUNTY, NEW MEXICO

prepared by the

NEW MEXICO ENVIRONMENT DEPARTMENT
HAZARDOUS WASTE BUREAU
2905 RODEO PARK DRIVE EAST, BUILDING 1
SANTA FE, NEW MEXICO 87505

January 2015

PERMIT ATTACHMENT A	FACILITY DESCRIPTION	1
A.1	INTRODUCTION.....	1
A.2	TA-I: HAZARDOUS WASTE HANDLING UNIT	1
A.2.1	HWHU Container Types	2
A.2.2	HWHU Designated Waste Management Areas	2
A.2.3	TA-I: HWHU Hazardous Waste Packaging Building 959	2
A.2.4	TA-I: HWHU Hazardous Waste Storage Building 958	3
A.2.5	TA-I: HWHU Modular Storage Buildings 958B and 958C.....	3
A.2.6	TA-I: HWHU Covered Open Storage Areas	4
A.2.7	TA-I: Unit Operations at the HWHU.....	4
A.2.8	TA-I: Preventing Hazards in Unloading and Loading of Waste at the HWHU	4
A.2.9	Preventing Run-Off or Run-On (Flooding) at the HWHU.....	5
A.2.9.1	TA-I: HWHU Catchment Pond Operating Procedures	5
A.2.10	HWHU Container Management Practices	5
A.3	TA-III: THE THERMAL TREATMENT UNIT	6
A.3.1	TA-III: TTU Hazardous Waste Management Area	7
A.3.2	TA-III: Unit Operations at the TTU.....	7
A.3.3	Preventing Hazards in Unloading and Loading at the TTU.....	8
A.3.4	Operation of Containment Systems at the TTU.....	8
A.4	TA-III: RADIOACTIVE AND MIXED WASTE MANAGEMENT UNIT	9
A.4.1	RMWMMU Designated Waste Management Areas	9
A.4.1.1	TA-III: Building 6920 at the RMWMMU.....	10
A.4.1.2	TA-III: Building 6921 at the RMWMMU.....	11
A.4.1.3	TA-III: Buildings 6925 and 6926 at the RMWMMU	12
A.4.1.4	TA-III: RMWMMU Modular Storage Buildings (TP150 and TP153)	12
A.4.1.5	TA-III: Outdoor Waste Storage Area of the RMWMMU	12
A.4.2	TA-III: RMWMMU Container Management Practices	13
A.4.3	TA-III: Preventing Hazards in Loading/Unloading at the RMWMMU	13
A.4.4	TA-III: Preventing Run-On and Run-Off (or Flooding) at the RMWMMU	13
A.4.5	TA-III: Treatment Operations at the RMWMMU	14
A.4.5.1	Chemical Deactivation	15
A.4.5.2	Thermal Deactivation	16
A.4.5.3	Stabilization and Solidification.....	17
A.4.5.4	Amalgamation	18
A.4.5.5	Macro-Encapsulation.....	18
A.4.5.6	Physical Treatment	19
A.4.6	Treatment Effectiveness	19
A.4.6.1	Chemical Deactivation	20

A.4.6.2	Thermal Deactivation	20
A.4.6.3	Stabilization and Solidification.....	20
A.4.6.4	Amalgamation	21
A.4.6.5	Macro-encapsulation.....	21
A.4.6.6	Physical Treatment	21
A.5	TA-V: THE AUXILIARY HOT CELL	21
A.5.1	TA-V: Designated Waste Management Areas at the AHCU.....	21
A.5.1.1	TA-V: AHCU Hot Cell	22
A.5.1.2	TA-V: AHCU Work Area and Fume Hood	22
A.5.1.3	TA-V: AHCU Storage Silos.....	22
A.5.1.4	TA-V: AHCU Container Storage	23
A.5.1.5	TA-V: AHCU Container Management Practices	23
A.5.2	TA-V: Preventing Hazards in Loading/Unloading at the AHCU	24
A.5.3	TA-V: Preventing Run-on and Run-Off (or Flooding) at the AHCU	24
A.5.4	TA-V: Treatment Operations at the AHCU.....	24
A.6	MANZANO BASE: MANZANO STORAGE BUNKERS.....	25
A.6.1	Manzano Base: Designated Waste Management Areas at the MSB.....	25
A.6.2	Manzano Base: MSB Type B Bunker (37034)	25
A.6.3	Manzano Base: MSB Type C Bunker (37118)	26
A.6.4	Manzano Base: MSB Type D Bunkers (37045, 37055, and 37057).....	26
A.6.5	Manzano Base: Unit Operations at the Manzano Storage Bunkers	26
A.6.6	Manzano Base: MSB Container Management Practices	27
A.6.7	Manzano Base: Preventing Hazards During Loading/Unloading at the MSB	27
A.6.8	Manzano Base: Preventing Run-on and Run-Off (or Flooding) at the MSB	27
A.7	THE CORRECTIVE ACTION MANAGEMENT UNIT	28
A.7.1	CAMU Access	28
A.7.2	General Description of the CAMU	28
A.7.3	CAMU Leachate Management	29
A.7.4	CAMU Leachate Collection and Removal	29
A.7.5	CAMU Less-Than-90-Day Accumulation Area	29
A.7.6	Description of the CAMU Containment Cell	29
A.7.6.1	Containment Cell Liner System.....	30
A.7.6.2	Bottom Liner Components.....	30
A.7.6.3	The Leachate Collection and Removal System	30
A.7.6.4	Geomembrane Liner	30
A.7.6.5	Geosynthetic Clay Liner	31
A.7.6.6	Sidewall Liner Components	31
A.7.6.7	Protective Cover Sheet	31

A.7.6.8	Geomembrane.....	31
A.7.6.9	GCL.....	31
A.7.6.10	Prepared Subgrade	31
A.7.6.11	Final Cover System.....	31
A.7.6.12	Topsoil and Native Soil Blend Layers	32
A.7.6.13	Filter Sand/Pea Gravel Layers	32
A.7.6.14	Bedding Sand Layer and HDPE Liner	32
A.7.6.15	Vadose Zone Monitoring System (VZMS)	32
A.7.6.16	Primary Subliner Monitoring Subsystem	33
A.7.6.17	VSA Monitoring Subsystem	33
A.7.6.18	Chemical Waste Landfill and Sanitary Sewer Line Monitoring Subsystem	33
PERMIT ATTACHMENT B AUTHORIZED WASTES		34
B.1	INTRODUCTION.....	34
B.2	AUTHORIZED WASTES FOR THE THERMAL TREATMENT UNIT.....	34
B.3	AUTHORIZED WASTES FOR TREATMENT AND/OR STORAGE AT THE HAZARDOUS WASTE HANDLING UNIT, THE RADIOACTIVE AND MIXED WASTE MANAGEMENT UNIT, THE AUXILIARY HOT CELL UNIT, AND THE MANZANO STORAGE BUNKERS.....	34
PERMIT ATTACHMENT C WASTE ANALYSIS PLAN		47
C.1	INTRODUCTION.....	47
C.2	WASTE TYPES GENERATED AT THE FACILITY.....	47
C.2.1	Laboratory Chemical Waste	51
C.2.2	Contaminated Used Oil.....	51
C.2.3	Process Wastes.....	51
C.2.4	Explosive (Reactive) Waste.....	51
C.2.5	Batteries	52
C.2.6	Elemental Lead	52
C.2.7	Unknown Liquids and Solids.....	52
C.2.8	Contaminated Soil	52
C.2.9	Debris.....	52
C.2.10	Leachate and Decontamination, Purge, and Treatment Waters	53
C.2.11	Treated Waste and Treatment Residues	53
C.2.12	Containment System Liquids.....	53
C.3	WASTE CHARACTERIZATION PROCEDURES.....	53
C.3.1	Waste Characterization Process	53
C.3.2	Characterization of Unknown Wastes	54
C.3.3	Characterization of Blended Wastes	55
C.3.4	Characterization of Wastes Treated at the Permitted Units	61
C.3.4.1	Characterization of Waste to be treated at the Thermal Treatment Unit	61

C.3.4.2	Characterization of Wastes to be treated at the RMWMU and AHCU	61
C.3.4.3	Characterization of Treated Wastes and Treatment Residues	62
C.3.4.4	Characterization of Treated Waste Residues at the TTU	62
C.3.4.5	Characterization of Treated Wastes and Treatment Residues Generated at the RMWMU and the AHCU	63
C.4	VERIFICATION AND RE-EVALUATION FREQUENCIES	64
C.4.1	Verification of Wastes	64
C.4.2	Re-evaluation of Waste Streams	64
C.5	USE OF ACCEPTABLE KNOWLEDGE	64
C.5.1	Process Knowledge	65
C.6	WASTE SAMPLING AND ANALYSIS	70
C.6.1	Quality Assurance/Quality Control	70
C.6.2	Waste Sampling	70
C.6.3	Sample Handling, Preservation, and Storage	71
C.6.4	Analytical Laboratory Selection and Analytical Methods	72
C.7	ORGANIC AIR EMISSION REQUIREMENTS	77
C.8	PROCEDURES FOR ACCEPTANCE OF WASTE FROM OFF-SITE SOURCES.....	77
C.9	RECORDS	78
C.10	REFERENCES.....	78
PERMIT ATTACHMENT D	CONTINGENCY PLAN.....	79
D.1	INTRODUCTION.....	79
D.2	DISTRIBUTION OF CONTINGENCY PLAN AND AMENDMENTS.....	79
D.3	EMERGENCY RESPONSE personnel and support agreements	79
D.3.1	Emergency Coordinator and Responsibilities	79
D.3.2	Emergency Response Groups	80
D.3.3	Emergency Chain of Command.....	81
D.3.4	Support Agreements and Coordination with Outside Agencies.....	81
D.4	EMERGENCY EQUIPMENT.....	81
^a	The Permittees are not a direct party to the agreement between the U.S. Forest Service and Kirtland Air Force Base.	82
D.5	CONTINGENCY PLAN IMPLEMENTATION	82
D.6	EMERGENCIES.....	84
D.6.1	Fire.....	84
D.6.2	Explosion	86
D.6.3	Uncontrolled Release	86
D.7	EVACUATION	87
D.8	COORDINATION WITH OFF-SITE PARTIES AND EMERGENCY NOTIFICATION	88
D.8.1	Post-Emergency Actions.....	88

D.9	EMERGENCY RESPONSE RECORDS AND REPORTS	88
D.10	ADDITIONAL CONTINGENCY PLAN INFORMATION FOR THE HAZARDOUS WASTE HANDLING UNIT.....	89
D.11	ADDITIONAL CONTINGENCY PLAN INFORMATION FOR THE THERMAL TREATMENT UNIT	92
D.12	ADDITIONAL CONTINGENCY PLAN INFORMATION FOR THE RADIOACTIVE AND MIXED WASTE MANAGEMENT UNIT	92
D.13	ADDITIONAL CONTINGENCY PLAN INFORMATION FOR THE AUXILIARY HOT CELL UNIT	98
D.14	ADDITIONAL CONTINGENCY PLAN INFORMATION FOR THE MANZANO STORAGE BUNKERS.....	101
D.15	ADDITIONAL CONTINGENCY PLAN INFORMATION FOR THE CAMU	101
PERMIT ATTACHMENT E INSPECTION PLAN		104
E.1	INTRODUCTION.....	104
E.2	INSPECTION RECORDS	104
E.3	REMEDIAL ACTION.....	104
E.4	INSPECTION SCHEDULE AND REQUIREMENTS FOR PERMITTED UNITS	105
E.4.1	Daily Inspection.....	105
E.4.2	Weekly Inspection	105
E.4.3	Monthly Inspection	105
E.5	INSPECTION PLAN FOR THE HAZARDOUS WASTE HANDLING UNIT	106
E.6	INSPECTION PLAN FOR THE THERMAL TREATMENT UNIT	107
E.7	INSPECTION PLAN FOR THE RADIOACTIVE AND MIXED WASTE MANAGEMENT UNIT	109
E.8	INSPECTION PLAN FOR THE AUXILIARY HOT CELL UNIT	111
E.9	INSPECTION PLAN FOR THE MANZANO STORAGE BUNKERS	113
E.10	INSPECTION PLAN FOR THE CORRECTIVE ACTION MANAGEMENT UNIT.....	115
E.10.1	Inspection, Maintenance, and Repair Activities and Frequencies	115
E.10.2	Final Cover System Inspection	115
E.10.3	Storm-Water Diversion Structures Inspection	116
E.10.4	LCRS Inspection.....	116
E.10.5	VZMS Inspection.....	116
E.10.6	Security Fence Inspection	116
PERMIT ATTACHMENT F PERSONNEL TRAINING PLAN.....		119
F.1	INTRODUCTION.....	119
F.2	HAZARDOUS WASTE MANAGEMENT RESPONSIBILITIES	119
F.3	TRAINING CONTENT, FREQUENCY, AND TECHNIQUES	119

F.4	JOB TITLE/JOB DESCRIPTION AND TRAINING RECORDS.....	119
F.5	TRAINING DIRECTOR.....	120
F.6	EMERGENCY TRAINING.....	125
F.7	IMPLEMENTATION OF TRAINING PROGRAMS	125
PERMIT ATTACHMENT G CLOSURE PLANS		137
G.1	CLOSURE PLAN FOR THE HAZARDOUS WASTE HANDLING UNIT ...	138
G.1.1	INTRODUCTION	139
G.1.2	CLOSURE PROCESS	139
G.1.3	SAMPLING AND ANALYSIS PLAN	140
G.1.4	AMENDMENT TO THIS CLOSURE PLAN.....	141
G.1.5	WASTES GENERATED FROM CLOSURE ACTIVITIES	142
G.1.6	CLOSURE REPORT AND CERTIFICATION	142
G.2	CLOSURE PLAN FOR THE THERMAL TREATMENT UNIT	147
G.2.1	INTRODUCTION	148
G.2.2	CLOSURE PROCESS	148
G.2.3	SAMPLING AND ANALYSIS PLAN	149
G.2.4	AMENDMENT TO THIS CLOSURE PLAN.....	150
G.2.5	WASTES GENERATED FROM CLOSURE ACTIVITIES	150
G.2.6	CLOSURE REPORT AND CERTIFICATION	150
G.3	CLOSURE PLAN FOR THE RADIOACTIVE AND MIXED WASTE MANAGEMENT UNIT	153
G.3.1	INTRODUCTION	154
G.3.2	CLOSURE PROCESS	154
G.3.3	SAMPLING and analysis plan	155
G.3.4	AMENDMENT TO THIS CLOSURE PLAN.....	157
G.3.5	WASTES GENERATED FROM CLOSURE ACTIVITIES	157
G.3.6	CLOSURE REPORT AND CERTIFICATION	157
G.4	CLOSURE PLAN FOR THE AUXILIARY HOT CELL UNIT	163
G.4.1	INTRODUCTION	164
G.4.2	CLOSURE PROCESS	164
G.4.3	SAMPLING AND ANALYSIS PLAN	165
G.4.4	AMENDMENT TO THIS CLOSURE PLAN.....	166
G.4.5	WASTES GENERATED FROM CLOSURE ACTIVITIES	166
G.4.6	CLOSURE REPORT AND CERTIFICATION	166
G.5	CLOSURE PLAN FOR THE MANZANO STORAGE BUNKERS.....	168
G.5.1	INTRODUCTION	170
G.5.2	CLOSURE PROCESS	170
G.5.3	SAMPLING AND ANALYSIS PLAN	171

G.5.4	AMENDMENT TO THIS CLOSURE PLAN	173
G.5.5	WASTES GENERATED FROM CLOSURE ACTIVITIES	173
G.5.6	CLOSURE REPORT AND CERTIFICATION	173
PERMIT ATTACHMENT H POST-CLOSURE CARE PLAN FOR THE CORRECTIVE ACTION MANAGEMENT UNIT		177
H.1	INTRODUCTION.....	177
H.2	STORM-WATER DIVERSION STRUCTURES	177
H.3	SECURITY	177
H.4	MAINTENANCE AND REPAIRS.....	178
H.4.1	Final Cover System.....	178
H.4.2	Storm-Water Diversion Structures.....	178
H.4.3	LCRS	179
H.4.4	VZMS	179
H.4.5	Security Fencing and Signage.....	179
H.5	VADOSE ZONE MONITORING SYSTEM LEAK DETECTION MONITORING FREQUENCY AND ASSESSMENT	179
H.5.1	Frequency	180
H.5.2	Assessment	181
H.5.2.1	Soil Moisture.....	181
H.5.2.2	Soil Gas	181
H.5.2.3	Corrective Action	181
H.6	SAMPLING AND ANALYSIS PLAN FOR THE CAMU PRIMARY SUBLINER MONITORING SYSTEM	182
H.6.1	Monitoring Methods	182
H.6.2	CPN 503DR Hydroprobe Moisture Depth Gauge QA/QC and Correlation	183
H.7	SAMPLING AND ANALYSIS PLAN FOR THE CAMU VERTICAL SENSOR ARRAY MONITORING SYSTEM	183
H.7.1	Monitoring and Sampling Strategy	184
H.7.2	Sampling Methods and Analytical Procedures	184
H.7.3	Time-Domain Reflectometer and Data Acquisition Software and QA/QC	184
H.8	SAMPLING AND ANALYSIS PLAN FOR THE CHEMICAL WASTE LANDFILL AND SANITARY SEWER LINE MONITORING SYSTEM AT THE CAMU.....	184
H.8.1	Monitoring and Sampling Strategy	185
H.8.2	Sampling Methods and Analytical Procedures	185
H.9	ANNUAL REPORT	186
H.10	CERTIFICATION OF COMPLETION OF POST-CLOSURE CARE	186
PERMIT ATTACHMENT I COMPLIANCE SCHEDULES		187

PERMIT ATTACHMENT J	HAZARDOUS AND MIXED WASTE MANAGEMENT	
UNITS	188	
J.1	ACTIVE PORTION OF THE FACILITY	188
PERMIT ATTACHMENT K	SOLID WASTE MANAGEMENT UNITS AND AREAS	
OF CONCERN	192	
PERMIT ATTACHMENT L	FIGURES	204
PERMIT ATTACHMENT M	LONG-TERM MONITORING AND MAINTENANCE	
	PLAN FOR SOLID WASTE MANAGEMENT UNITS AND AREAS OF	
	CONCERN GRANTED CORRECTIVE ACTION COMPLETE WITH	
	CONTROLS	212
M.1	INTRODUCTION.....	212
M.2	INSTITUTIONAL CONTROLS	213
M.2.1	Administrative Controls.....	213
M.2.2	Physical Controls	213
M.3	MAINTENANCE OF INSTITUTIONAL CONTROLS.....	218
M.3.1	Maintenance of Administrative Controls	218
M.3.2	Maintenance of Physical Controls	218
M.4	LTMMP REPORTING REQUIREMENTS	219